



MicroLED INSTALLATION SOW

This Statement of Work ("SOW") is issued by AWALL LLC, to define a full scope of installation services for MicroLED display walls, including mounting, commissioning, cleanup, and customer handoff.

Project Details

Project Name:	
Project Objective:	
Project Address:	
Projected Start Date:	
Estimated Duration:	
AWALL Project Manager:	

Scope of Work

- Site review, measurement, and preparation for installation
- Mount structure alignment and X/Y/Z adjustment (fine-tuning horizontal, vertical, and depth alignment)
- Installation of MicroLED display cabinets with all signal and power connections
- Module installation, pixel/diode QC
- System testing, commissioning, and calibration/firmware update if needed
- Site cleanup (trash/pallets prepped for end-customer disposal)
- Install handoff with customer orientation

Site Readiness Requirements

Client is responsible for ensuring the site is ready for installation:

- Wall/floor structure including **FURNITURE GRADE PLYWOOD BACKER**
- All required power circuits installed at locations as directed by AWALL
- Cat6 network lines run from the installation wall to the location of the processor
- Physical access to clean and dust free site
- All municipal/permit approvals prior to AWALL's scheduled install date

Provided Services

- Travel, lodging, local transportation, per diem included unless noted
- Deployment of lead and tech installer(s)
- Mounting and alignment per AWALL standards
- Signal and power cable routing per best practices
- System commissioning and out of box calibration
- Color balance and tuning as needed or requested by customer at initial setup
- Debris removal and cleanup

Inclusions

- On-site installation labor (non-union)
- Standard business hours: 8:00 AM - 5:00 PM, Mon–Fri
- Installation of: AWALL's mounting bracket, MicroLED display, local power/signal cables at display, and initial system testing

Exclusions

- Structural wall integrity verification prior to mount installation
- Staging, unboxing, or moving display panels/mounts into the install area
- Scissor lifts/genie lifts or specialized equipment (available by quote)
- Additional color calibration unless purchased in advance
- Automation system integration and programming
- AV system integration (audio, video distribution or switching, AV receivers) beyond the LED wall processor inputs
- Delays or extended time due to unforeseen circumstances billed as extra
- Overtime labor outside regular hours unless pre-approved
- Optional add-ons by request: survey/report, lift rentals, project management, extended support, additional calibrations past initial setup

Optional Add-ons

- Additional color calibration past initial performed at setup to customer satisfaction
- Weekend/Holiday/Out-of-Town Installations
- Site Survey & Reporting
- Lift Rentals
- On-site Project Management
- Extended System Support

Cost to dealer [choose 1]

- ✓ \$3000 for one installer
- ✓ \$5000 for two installers

Project Notes

SOW Acknowledgement Signatures

By signing below, all parties acknowledge and agree to the terms of this Statement of Work. Signatures must be obtained before any installation work begins.

AWALL LLC Print Name:	
Subcontractor/Owner Print Name:	
Date:	

Installation Commissioning

[To be completed post installation at final project commissioning - tested and verified]

Installation Notes

Installation Complete Signatures

AWALL LLC: Print Name:	
Subcontractor/Owner: Print Name:	
Date:	